

« Back



Procuring Agency Information

 Uzair Ahmed

 Senior Executive Procurement

Procurement

 Pakistan Single Window

+92-219-933-2944

 uzair.ahmed@psw.gov.pk

5th Floor, Bahria Complex-I building, M.T. Khan Road, Karachi.

Reference No. P165051

For Lot as a Whole



Estimated Cost *

Title		Quantity	Unit	Delivery Schedule	Specification/Requirements
	Dismantling & Reinstallation of Gypsum Ceiling	500	Square Foot		
	1/2 Inch AC Copper Pipe Insulation with Install	600	Foot		
	1/4 Inch AC Copper Pipe Insulation with Install	600	Foot		
	CABLE TRAYS (12	100	Foot		

Scope of Work *

B *I* U I_x | $\frac{1}{2}$ $\frac{3}{4}$ $\frac{5}{8}$ $\frac{7}{8}$ |   |   |   | Normal ▼



SCOPE OF WORK

AC Pipe Separation, Dedicated Tray Installation & Re-Insulation

Location: 5th Floor Bahria Complex - I

The existing electrical cable tray is approximately 80 Rft in length and currently contains electrical cables along with 8 Nos. AC pipes. Due to inadequate/seepage of insulation, moisture/condensation is being observed on the AC pipes. The AC pipes are therefore required to be separated from the electrical cable tray and properly re-insulated.

Scope of Work

Dismantling of False Ceiling:

Carefully dismantle the existing 2' x 2' false ceiling wherever required to access the AC pipes and cable tray. Approximate area: 500 Sq. Ft.

Dedicated AC Pipe Tray:

Supply and install a separate dedicated tray/support system for the 8 Nos. AC pipes, including all required brackets, supports, clamps, fasteners and accessories.

Approximate tray area: 100 Sq. Ft.

AC Pipe Shifting & Re-routing:

Carefully remove the AC pipes from the existing common electrical cable tray and re-route/fix them in the new dedicated AC pipe tray. Approximate existing route: 80 Rft.

Complete AC Pipe Re-insulation:

Provide and install new high-quality HVAC-grade insulation on all 8 AC pipes for an approximate total length of 600 Rft. Insulation shall be continuous and properly sealed to prevent condensation and moisture formation.

Joint & Vapour Sealing:

All insulation joints, bends, connections and termination points shall be properly sealed using suitable adhesive/tape/vapour barrier to ensure a moisture-proof finish.

False Ceiling Re-installation:

Reinstall the dismantled 2' x 2' false ceiling after completion of all AC pipe/tray works, ensuring proper alignment and neat finishing. Approximate area: 500 Sq. Ft.

Testing & Housekeeping:

body p

Maximum 20000 characters allowed

⚠ This procurement has been published. You can no longer modify any data.